


PURCHASE ORDER EXHIBIT FOR WORK ORDER NO. 2019-02
 2018 & 2019 EVALUATION AND REHABILITATION OF WASTEWATER COLLECTION SYSTEM
 CITY OF JOPLIN, MISSOURI

ITEM NO.	NO. OF UNITS	UNIT	DESCRIPTION	UNIT PRICE	EXTENDED
66	1	LS	Mobilization	\$ 8,000.00	\$ 8,000
67	6,000	LF	8" Dia. CIPP	\$ 23.25	\$ 139,500
69	500	LF	10" Dia. CIPP	\$ 26.25	\$ 13,125
90	1	LS	Mobilization	\$ 2,000.00	\$ 2,000
91	3	EA	CIPP Point Repair	\$ 1,600.00	\$ 4,800
115	1	LS	Mobilization	\$ 2,500.00	\$ 2,500
116	35	EA	Setup Per Manhole to Manhole Segment	\$ 500.00	\$ 17,500
117A	55	EA	UV Cured LCR 8"-12" Main, 4" to 6" Lateral, 18" Long	\$ 1,000.00	\$ 55,000
132	1	LS	Mobilization	\$ 1,100.00	\$ 1,100
133	5	EA	Manhole Frame and Cover Replacement- Under Turf	\$ 910.00	\$ 4,550
134	20	EA	Manhole Frame and Cover Replacement- Under Alley	\$ 1,100.00	\$ 22,000
135	20	EA	Manhole Frame and Cover Replacement- Under Pavement	\$ 2,750.00	\$ 55,000
139	360	VF	4' Manhole Renovation - Cementitious w/ Antimicrobial Additive	\$ 175.00	\$ 63,000
154	1	LS	Mobilization	\$ 1,200.00	\$ 1,200
155	45	EA	Flexible Chimney Sealant	\$ 495.00	\$ 22,275
165	1	LS	Mobilization	\$ 1,100.00	\$ 1,100
168	3	EA	Point Repair Under Turf 6-12' Deep (10' min.)	\$ 2,000.00	\$ 6,000
169	20	LF	Additional 6-12' Deep Point Repair Under Turf	\$ 120.00	\$ 2,400
174	5	EA	Point Repair Under Alleyway 6-12' Deep (10' min.)	\$ 3,100.00	\$ 15,500
175	100	LF	Additional 6-12' Deep Point Repair Under	\$ 168.00	\$ 16,800
180	5	EA	Point Repair Under Pavement 6-12' Deep (10' min.)	\$ 4,400.00	\$ 22,000
181	100	LF	Additional 6-12' Deep Point Repair Under Pavement	\$ 250.00	\$ 25,000
241	1	LS	Mobilization	\$ 1,100.00	\$ 1,100
243	5	EA	Open Trench Lateral Reconnection Under Turf 6-12' Deep	\$ 2,700.00	\$ 13,500
246	12	EA	Open Trench Lateral Reconnection Under Alleyway 6-12' Deep	\$ 3,400.00	\$ 40,800
249	12	EA	Open Trench Lateral Reconnection Under Pavement 6-12' Deep	\$ 5,200.00	\$ 62,400
282	25	LF	Open Trench Lateral Under Turf 6-12' Deep	\$ 85.00	\$ 2,125
285	60	LF	Open Trench Lateral Under Alleyway 6-12' Deep	\$ 100.00	\$ 6,000
288	60	LF	Open Trench Lateral Under Pavement 6-12' Deep	\$ 150.00	\$ 9,000
314	100	CY	Lead Contaminated Soil Disposal	\$ 13.50	\$ 1,350
330	4	EA	Trench Plug	\$ 1,200.00	\$ 4,800
			Construction Subtotal		\$ 641,425
			Performance and Payment Bonds (1.5%)		\$ 9,621
			Construction Total		\$ 651,046



**PURCHASE ORDER EXHIBIT
FOR
WORK ORDER NO. 2019-02**

ZORA

ROYAL HEIGHTS AREA

EAST HIGHLAND AREA

LONE ELM

MAIN

RANGELINE

7TH

